

May 29, 2020

Re: TALBOT COUNTY PUBLIC SCHOOLS SECURITY VESTIBULE INSTALLATION  
(PROJECT #20.0800-1) REQUEST FOR PROPOSAL (RFP) ADDENDUM

ADDENDUM #1:

The RFP document for the aforementioned project, advertised on May 11, 2020, is being amended based on the following information:

- A. Contractor Response Form – The RFP states that the Contractor Response Form shall be “completed and submitted with the proposal”. This requirement is being altered to allow for the submission of the associated documentation prior to contract ratification; therefore, this requirement would only apply to the successful contractor.
- B. Fire Alarm and Security System Service Provider – TCPS contracts with Delmarva Time and Control as the monitor of our fire and security systems.
- C. Equipment Specifications – All equipment shall be compatible with existing systems and the following general equipment specifications apply:
  - Card Readers: Provide HID Global HID RP40 Multiclass readers, except provide RP15 where mullion mounts are indicated. Coordinate with existing system, provide additional power supplies as required.
  - Videophones: Provide Aiphone IS-IPDV video door station, connect to existing system.
  - Other: Provide Bosch DS160 request-to-exit detectors as shown.
- D. St. Michaels Middle/High School Security Vestibule Clarification – The “metal mesh panel” specified for the new vestibule shall be the following:
  - Provide Direct Metals DMSJD-3 or equal stainless-steel mesh, supported on 2" D x 1/8" painted steel tees at 48" o.c.
  - The direct link is as follows: <https://www.directmetals.com/wp-content/uploads/2018/11/DMSJD-3.pdf>
- E. Sign-In Sheet – The sign in sheet from the pre-proposal meeting is attached.

**END OF ADDENDUM #1**

